

PENGUMUMAN PELELANGAN

NOMOR : 375.PENG/PJBS/2016

TENTANG

PENGADAAN PORTABLE PURIFIER OIL TRAFU (ESI – ST6, 6000 I/hr HIGH VACUUM PURIFIER)

Tim Pengadaan Barang/Jasa PT Pembangkitan Jawa Bali Services akan melaksanakan Pelelangan Pengadaan Portable Purifier Oil Trafo (ESI – ST6, 6000 I/hr High Vacuum Purifier), dengan persyaratan sebagai berikut :

1 Persyaratan Peserta Lelang :

Persyaratan Penyedia Barang/Jasa yang dapat mengikuti Pelelangan ini sebagai berikut :

- a. Memiliki Surat Ijin Usaha Perdagangan (SIUP) yang masih berlaku,
- b. Manufacture/agen di Indonesia
- c. Bilamana bukan manufacture/agen di Indonesia, didukung oleh agen di Indonesia yang dibuktikan dengan surat dukungan
- d. Penyedia Barang/Jasa tidak sedang menjalani sanksi Blacklist di Lingkungan PT PJB Services dan PT PJB.

2 Pelaksanaan Pengadaan

- a. Pendaftaran dan Pengambilan Dokumen :

Tanggal : 06 s.d 12 Oktober 2016

Waktu : 09.00 s.d. 14.00 WIB

Tempat : PT PEMBANGKITAN JAWA-BALI SERVICES

Jalan Raya Bandara Juanda No. 17 Sidoarjo

- b. Membayar biaya dokumen sebesar Rp 250.000,00

- c. Dokumen Pengadaan dapat diambil dalam bentuk *hard copy* dan *soft copy*.

3 Spesifikasi Barang

Sesuai daftar terlampir

Demikian disampaikan untuk menjadi perhatian.

Sidoarjo, 06 Oktober 2016

Tim Pengadaan Barang/ Jasa PT. PJB Services

Catatan :

Peserta yang mendaftar diharapkan membawa flashdisk apabila membutuhkan softcopy dokumen

Lampiran Pengumuman	:	375.PENG/PJBS/2016
Tanggal	:	06 OKTOBER 2016

SPEKIFIKASI BARANG YANG DIMINTAKAN PENAWARAN

NO	NAMA BARANG / JASA	JUMLAH	SATUAN	HARGA SATUAN (Rp)	JUMLAH HARGA (Rp)
I	PENGADAAN PORTABLE PURIFIER OIL TRAFU (ESI – ST6, 6000 l/hr HIGH VACUUM PURIFIER)	1	Set		
	<p>Merk : ESI – ST6, 6000 l/hr High Vacuum Purifier</p> <p>Pipe Work: All pipe work, the vacuum chamber and the filter housings are made from high quality stainless steel.</p> <p>Power Requirements 415 (375-420) V AC 3 phase, 50 Hz, 160 amps (max)</p> <p>Control Box</p> <ul style="list-style-type: none"> • Weather Proof Painted Steel Rittal Enclosure. • Burkert Electronic Flow Meter • Allen Bradley Temperature Controller with Digital read-out. • Vacuum Gauge. • Filter Pressure Gauges. • Elapsed Time Hour Meter for Vacuum Pumps. • Motor Start and Stop Buttons. • Run Light Indicators and Emergency Stop Button. • Heater and Pump Trip Indicators 				
	<p>Inlet Pump Tuthil gear pump with mechanical seal and internal pressure by pass with Brook Crompton 2.2 kW, 1500 rpm, 3 phase motor. with speed control.</p> <p>Outlet Pumps Calpeda centrifugal pump with 2.2 kW, 2900 rpm, 3 phase motor</p> <p>Vacuum Pumps: • Backing Pump PVR Type EU capacity 105 m3/hr, 0.5 mbar ultimate vacuum, 3 kW, 3 phase motor • Booster Pump FRU 11.4 HV capacity 600 m3/hr 0.01mbar ultimate vacuum, 2.2kW, 3 phase motor.</p> <p>Oil Heater 96 kW hermetically sealed immersion heaters controlled by a 4 stage switches and a temperature controller/display module</p>				
	<p>Indication Filter inlet and outlet pressure, vacuum, temperature, oil flow in litres/min plus total litres since reset, plant status, alarm and fault indication.</p> <p>Oil Sample Ports: Sample ports for inlet and outlet oil quality are supplied with this unit.</p> <p>Dimensions: • Length: 2100 mm; width: 1450 mm; height 1820 mm • Weight: 1800 kg • Base Tray Capacity: 200 litres.</p>				
	<p>Include :</p> <ul style="list-style-type: none"> - In Line Moisture Meters (in & out) - Heavy Duty, Weather Proof Cover - Mounted on 2 axle Trailer - Dielectric Strength Test Tool (Non China) Compatible Dielectric Strength Test for Oil Transformer, IEC Standard. - Tool Kit Hose, Connection Kit to Transformer, etc - Oil filter 2 sets (4 pcs) 	1 1 1 1 1 1	Lot Lot Lot Lot Lot Lot		
	<p>Training/Pelatihan</p> <ul style="list-style-type: none"> - Training meliputi pengoperasian dan pemeliharaan alat - Minimal 2 (dua) hari Training in class dan on site training untuk minimal 15 orang - Training diberikan oleh Trainer bersertifikat dari manufacture - Certificate untuk peserta training (termasuk) 	1	Lot		
	<p>Catatan :</p> <ul style="list-style-type: none"> - Koordinasi dengan unit (administratif dan biaya) untuk on site training menjadi tanggung jawab pelaksana pekerjaan. Dan segala peralatan penunjang dilakukannya pengujian disediakan penyedia saat User Training berlangsung 				
				TOTAL	
				PPN 10%	
				JUMLAH TOTAL	