

PENGUMUMAN PELELANGAN TERBUKA

NOMOR 793.Peng/SCM/PJBS/2022

TENTANG

PENGADAAN JASA ADDITIONAL SCOPE ME PENGGANTIAN LINE PIPE CLOSE COOLING WATER UNIT 1 PLTU KETAPANG

Tim Pengadaan Barang/Jasa PT Pembangkitan Jawa Bali Services akan melaksanakan Pelelangan Pengadaan Jasa Additional Scope ME Penggantian Line Pipe Close Cooling Water Unit 1 PLTU Ketapang dengan persyaratan sebagai berikut :

1. Persyaratan Peserta Lelang

- Memiliki Surat Ijin Usaha Perdagangan (SIUP) atau Izin Usaha Tetap (IUT) atau Nomor Induk Berusaha (NIB) yang masih berlaku
- Terdaftar dalam VMS PT PJB Services atau sedang dalam kepengurusan
- Telah dinyatakan lolos atau memiliki sertifikat CSMS PJB Group yang masih berlaku dengan kategori risiko moderate
- Telah memenuhi kewajiban perpajakan tahun terakhir
- Berpengalaman dalam pekerjaan jasa penggantian line pipe close cooling water minimal 1 (satu) pekerjaan serupa
- Memiliki personil yang kompeten
- Memiliki tools dalam kondisi baik untuk pelaksanaan pekerjaan jasa penggantian line pipe dan drain boiler

2. Pelaksanaan Pengadaan

- a. Pendaftaran dan Pengambilan Dokumen :

Hari/Tanggal : Selasa, 14 Juni 2022 sd Senin, 20 Juni 2022
Waktu : Pukul 10:00 s/d 15:00 WIB
Tempat : - PT. PEMBANGKITAN JAWA BALI SERVICES
Jl. Raya Bandara Juanda No 17
Desa Semambung, Gedangan
Sidoarjo
- Atau melalui email pengadaan@pjbservices.com

dengan diberi subyek :

SURAT PERNYATAAN MINAT PENGADAAN JASA ADDITIONAL SCOPE ME PENGGANTIAN LINE PIPE CLOSE COOLING WATER UNIT 1 PLTU KETAPANG

- b. Aanwijzing atau Penjelasan Dokumen:

Hari/Tanggal : Kamis, 16 Juni 2022
Waktu : Pukul 10:00 WIB
Tempat : - PT. PEMBANGKITAN JAWA BALI SERVICES
Jl. Raya Bandara Juanda No 17
Desa Semambung, Gedangan
Sidoarjo
- Atau Pelaksanaan penjelasan lelang dapat dilakukan melalui media daring atau Internet (email, video conference, dan lain-lain) yang akan diinformasikan berikutnya.

- c. Dokumen Pengadaan dapat di-email atau diambil dalam bentuk soft copy.

3. Spesifikasi Pekerjaan

Sesuai daftar Terlampir

Demikian disampaikan untuk menjadi perhatian.

Sidoarjo, 28 April 2022



HARGA PENAWARAN

NO	NAMA BARANG/JASA	JUMLAH	SATUAN	HARGA SATUAN (Rp)	JUMLAH HARGA (Rp)
1	Pengadaan Jasa Additional Scope ME Penggantian Line Pipe Close Cooling Water Unit 1 PLTU Ketapang	1	Lot		
Terbilang :				SUB TOTAL	
				PPN 11%	
				TOTAL HARGA	

PT PJB SERVICES

Jl. Raya Bandara Juanda No. 17, Sidoarjo 61253, Jawa Timur - Indonesia

Telp. (62-31) 8548391 - 8557909, Fax : (62-31) 8548360

e-mail : info@pjbservices.com

www.pjbservices.com



NO	NAMA BARANG/JASA	JUMLAH	SATUAN	HARGA SATUAN (Rp)	JUMLAH HARGA (Rp)
	Pengadaan Jasa Additional Scope ME Penggantian Line Pipe Close Cooling Water Unit 1 PLTU Ketapang				
1	Line Pipe Close Cooling Water to PA & SA Fan				
	Pipa SS 304, Uk 2 inch, Sch 40, Pjg line 84 meter	14	Batang		
	Elbow 90°, SS 304, Uk 2 inch, Sch 40	8	Ea		
	Tee, SS 304, Uk 2 inch, Sch 40	2	Ea		
	Pipa SS 304, Uk 3/4 inch, Sch 40, Pjg line 44 meter	8	Batang		
	Elbow 90°, SS 304, Uk 3/4 inch, Sch 40	24	Ea		
	Flange, SS 304, Uk 3/4 inch, Sch 40	16	Ea		
	Sight Glass, SS 304, Uk 3/4 inch (DN 20, PN 16)	4	Ea		
	Gate Valve, SS 304, Uk 3/4 inch (DN 20, PN 16, PCD 75 mm)	8	Ea		
	SWG, SS 304, Uk 3/4 inch (DN 20, PN 16)	16	Ea		
	Bolt & Nut SS 304	64	Ea		
	Support Line (Besi UNP SS 304, Uk 2 inch, Clamp SS 304 Uk 2 inch & 3/4 inch)	1	Lot		
	Repainting (cat Base Primer, Cat Marine Coating, Signal Green RAL 6032 dan Tinner)	1	Lot		
2	Line Pipe Close Cooling Water to Oil Cooler & BFP				
	Pipa SS 304, Uk 2 1/2 inch, Sch 40, Pjg line 66 meter	11	Batang		
	Reducer Pipa, SS 304, Uk 2 1/2 inch, Sch 40	2	Ea		
	Elbow 90°, SS 304, Uk 2 1/2 inch, Sch 40	2	Ea		
	Pipa SS 304, Uk 3/4 inch, Sch 40, Pjg line 18 meter	3	Batang		
	Tee, SS 304, Uk 3/4 inch, Sch 40	6	Ea		
	Elbow 90°, SS 304, Uk 3/4 inch, Sch 40	6	Ea		
	Flange, SS 304, Uk 3/4 inch, Sch 40	12	Ea		
	Sight Glass, SS 304, Uk 3/4 inch (DN 20, PN 16)	3	Ea		
	Gate Valve, SS 304, Uk 3/4 inch (DN 20, PN 16, PCD 75 mm)	6	Ea		
	SWG, SS 304, Uk 3/4 inch (DN 20, PN 16)	12	Ea		
	Bolt & Nut SS 304	48	Ea		
	Pipa SS 304, Uk 1/2 inch, Sch 40, Pjg line 18 meter	3	Batang		
	Elbow 90°, SS 304, Uk 1/2 inch, Sch 40	24	Ea		
	Support Line (Besi UNP SS 304, Uk 2 inch, Clamp SS 304 Uk 2 inch & 3/4 inch)	1	Lot		
	Repainting (cat Base Primer, Cat Marine Coating, Signal Green RAL 6032 dan Tinner)	1	Lot		
3	Line Pipe Close Cooling Water to ID Fan				
	Pipa SS 304, Uk 2 inch, Sch 40, Pjg line 50 meter	10	Batang		
	Elbow 90°, SS 304, Uk 2 inch, Sch 40	6	Ea		
	Elbow 45°, SS 304, Uk 2 inch, Sch 40	4	Ea		
	Reducer Pipa, SS 304, Uk 2 inch to 3/4 inch, Sch 40	2	Ea		
	Pipa SS 304, Uk 3/4 inch, Sch 40, Pjg line 96 meter	16	Batang		
	Elbow 90°, SS 304, Uk 3/4 inch, Sch 40	15	Ea		
	Flange, SS 304, Uk 3/4 inch, Sch 40	8	Ea		
	Tee, SS 304, Uk 3/4 inch, Sch 40	6	Ea		
	Sight Glass, SS 304, Uk 3/4 inch (DN 20, PN 16)	2	Ea		
	Gate Valve, SS 304, Uk 3/4 inch (DN 20, PN 16, PCD 75 mm)	4	Ea		
	SWG, SS 304, Uk 3/4 inch (DN 20, PN 16)	8	Ea		
	Bolt & Nut SS 304	32	Ea		
	Support Line (Besi UNP SS 304, Uk 2 inch, Clamp SS 304 Uk 2 inch & 3/4 inch)	1	Lot		
	Repainting (cat Base Primer, Cat Marine Coating, Signal Green RAL 6032 dan Tinner)	1	Lot		



4	Line Pipe Close Cooling Water to HP Fan			
	Pipa SS 304, Uk 2 inch, Sch 40, Pjg line 18 meter	3	Batang	
	Elbow 90°, SS 304, Uk 2 inch, Sch 40	2	Ea	
	Pipa SS 304, Uk 3/4 inch, Sch 40, Pjg line 12 meter	2	Batang	
	Elbow 90°, SS 304, Uk 3/4 inch, Sch 40	8	Ea	
	Support Line (Besi UNP SS 304, Uk 2 inch, Clamp SS 304 Uk 2 inch & 3/4 inch)	1	Lot	
	Repainting (cat Base Primer, Cat Marine Coating, Signal Green RAL 6032 dan Tinner)	1	Lot	
5	Line Pipe Close Cooling Water to Compressor			
	Pipa SS 304, Uk 1 inch, Sch 40, Pjg line 18 meter	3	Batang	
	Elbow 90°, SS 304, Uk 1 inch, Sch 40	6	Ea	
	Tee, SS 304, Uk 3/4 inch, Sch 40	2	Ea	
	Support (Besi UNP SS 304, Uk 2 inch, Clamp SS 304 Uk 1 inch)	1	Lot	
	Repainting (cat Base Primer, Cat Marine Coating, Signal Green RAL 6032 dan Tinner)	1	Lot	
6	Man Power			
	- Supervisor 1 orang	15	Mandays	
	- Quality Control 1 orang	15	Mandays	
	- Welder 4 orang	60	Mandays	
	- Fitter 4 orang	60	Mandays	
	- Helper 4 orang	60	Mandays	
	- Safety advisor 1 orang	15	Mandays	
7	Material Consumable	1	Set	
8	Peralatan K3	1	Set	
9	Mob Demob Tools	1	Lot	
10	Mob Demob Man Power	1	Lot	
11	Transportasi & Akomodasi Lokal			
	- Penginapan	1	Lot	
	- Sewa Kendaraan	1	Lot	
	- Konsumsi	1	Lot	
12	Test Antigen Masuk Unit	15	Orang	
	- Biaya material dan jasa dapat didetailkan di tabel berikut			
	- Harga sudah termasuk biaya protokol covid-19			
Terbilang :				SUB TOTAL
				PPN 11%
				TOTAL HARGA

